

SPECIAL NOTES FOR CHAIN LINK FENCING

ALL CHAIN LINK FENCING AND GATES SAHLL BE TACK WELDED IN THE FOLLOWING MANNER TO PREVENT VANDALISM AND THEFT:

EVERY OTHER NUT SHALL BE TACK WELDED TO BOLT THREADS. EVERY OTHER BRACE BAND SHALL BE TACK WELDED TO POSTS. ALL STRETCHER BARS SHALL BE TACK WELDED TO EVERY OTHER BRACE BAND. ALL BALL CAPS AND POST CAPS SHALL BE TACK WELDED TO POSTS. FENCE FABRIC SHALL BE TACK WELDED TO POSTS AND RAILS AT 3'-0" o.c.

COST OF TACK WELDING TO BE INCLUDED IN THE PAY UNIT FOR CHAIN LINK FENCE AND GATES.

FENCE NOTES:

1) DIMENSIONS INDICATED FOR PIPE, ROLL-FORMED, ARE OUTSIDE DIMENSIONS, **EXCLUSIVE OF COATINGS.**

2) FABRIC, POSTS, GATES AND ALL HARDWARE SHALL BE CONSTRUCTED OF GALVANIZED STEEL (SEE SPECIFICATIONS).

3) IF SOLID ROCK IS ENCOUNTERED, POSTS SHALL BE INSTALLED IN DRILLED HOLES IN THE ROCK AND GROUTED.

4) PULL SHALL NOT NOT BE APPLIED TO POSTS SET IN CONCRETE FOUNDATIONS UNTIL THE CONCRETE HAS CURED A MINIMUM OF 72 HOURS.

5) FENCE FABRIC SHALL FACE TOWARDS THE ROADWAY.

6) MILL CERTIFICATION FOR CHAIN-LINK FENCE MATERIALS SHALL BE SUBMITTED TO THE ENGINEER IN ACCORDANCE WITH THE SPECIFICATIONS.

7) GATES SHALL BE EQUIPPED WITH HEAVY DUTY LOCKS AND TWO SETS OF KEYS.

City of Jersey City
Division of Engineering 575 ROUTE 440 JERSEY CITY, NEW JERSEY 07305 CORPORATE SERVICE

NO. REVISIONS

CITY OF JERSEY CITY STANDARDS

NO. REVISIONS

William R. Goble, P.E.
Director
Division of Engineering
NJ P.E. Lic. No. 24798

DATE

Chain Link Fence

DRAWING

DESIGNED BY DRAWN BY CHECKED BY PROJECT NO. CADD FILE SCALE